

8 5/8" casing installation: 11"-5M BOP stack to be installed and tested by Yellow Jacket, Inc. to 3,000 psi before drilling the 8 5/8" casing shoe by Yellow Jacket, Inc. The BOP stack to consist of an annular BOP, blind ram BOP and one pipe ram BOP.

11. See Form 9-331C.

12. A. DST Program: (1) Strawn

B. Core: 60' of Strawn (10,815-10,875')

C. Mud Logging: Two Man Unit 2000'-TD

D. Wire Line Logs:

The following suite of logs will be run in both of the listed intervals:

GR/CNL/FDC/Cal	TD-2900' (GR/CNL to surf)
GR/Dual Laterolog& MSFL	TD-2900'

13. No abnormal pressures anticipated with bottom hole pressures at TD expected to be 4400 psi. Bottom hole temperature 169° F. No Hydrogen Sulfide expected in this know drilling area. No crooked hole or abnormal deviation problems.

14. Anticipated starting date to spud - on or before 11-28-86. Anticipated drilling time expected to be 33 (41 with DST & coring) days from surface to TD.

C. Nokes
11/13/86
0067c:100986

RECEIVED
JAN 12 1987
OCD
HOBBS OFFICE