

8. Testing, Logging and Coring Program:

Samples: 10' samples out from under surface casing to TD.

DST's: As warranted by drilling breaks and shows.

Coring: None.

Logging: CNL-LDT from TD to Casing, with GR-CNL up to surface;  
DLL (with minimum RxO) from TD to Casing.

9. No abnormal pressures or temperatures are anticipated.

10. Anticipated starting date: As soon as possible after approval.