

"DD" Federal -24- Well No. 3

Mud Program

<u>Depth</u>	<u>Type</u>	<u>Weight</u>	<u>Viscosity</u>
0 -1100'	Fresh Water	8.4	28
1100'-7400'	Fresh Water	8.4	28
7400'-8000'	Starch	8.8	30

Blowout preventer will be installed after surface casing is set. BOP will be tested each time it is installed on a casing string and operated at least once each 24-hour period during drilling.