

E) DIRECTIONAL DRILLING

No directional services anticipated.

POINT 7: ANTICIPATED RESERVOIR CONDITIONS

Normal pressured formations are anticipated throughout this well. H₂S is normally associated with Bone Spring production. For the safety of the personnel on location, H₂S monitoring, alarm, and safety equipment will be installed at 3200'.

POINT 8: OTHER PERTINENT INFORMATION

A) Auxiliary Equipment

Upper and lower kelly cocks. Full opening stab in valve on the rig floor.

B) Anticipated Starting Date

Upon approval

14 days drilling operations

6 days completion operations

FDC/mac
2-08-96