

Con't...

#### POINT 4: PRESSURE CONTROL EQUIPMENT (SEE ATTACHED DIAGRAM)

A function test of annular, pipe and blind rams to insure that the preventers are operating correctly will be performed on each trip. A function test is required only a minimum of once every 24 hours. See the attached diagrams for the minimum criteria for the choke manifold.

#### POINT 5: MUD PROGRAM

<u>DEPTH</u>	<u>MUD TYPE</u>	<u>WEIGHT</u>	<u>FV</u>	<u>PV</u>	<u>YP</u>	<u>FL</u>	<u>Ph</u>
0' - 300'	FW Spud	8.4 - 9.0	32-38	NC	NC	NC	9-10
300' - 1600'	Brine	9.8 - 10.2	28-32	NC	NC	NC	9-10
1600' - 6800'	Brine/Starch	10.0-10.2	29-32	NC	NC	<100	10

#### POINT 6: TECHNICAL STAGES OF OPERATION

##### A) TESTING

None anticipated.

##### B) LOGGING

GR-CNL from 300' to surface.

GR-CNL-LDT-PEF and GR-DLL-SFL from TD to 300'.

##### C) CONVENTIONAL CORING

None anticipated.

##### D) CEMENT

<u>INTERVAL</u> <u>SURFACE</u>	<u>AMOUNT SXS</u>	<u>FT OF</u> <u>FILL</u>	<u>TYPE</u>	<u>GALS/SX</u>	<u>PPG</u>	<u>FT<sup>3</sup>/SX</u>
0-300'	210 (100% excess circ to surface)	300'	Class "C" + 2% CaCl <sub>2</sub>	6.32	14.8	1.32

#### PRODUCTION

<u>1st Stage</u>						
<u>INTERVAL</u>	<u>AMOUNT SXS</u>	<u>FILL</u>	<u>TYPE</u>	<u>GALS/SX</u>	<u>PPG</u>	<u>FT<sup>3</sup>/SX</u>
2000-6800'	730 (50% excess)	4800'	Class "H" + 1.4% D-155 + 0.5% D604AM + 0.02% M45 + 3% D44 + 0.3% D13	8.8	14.00	1.66
<u>2nd Stage</u>						
<u>INTERVAL</u>	<u>AMOUNT SXS</u>	<u>FILL</u>	<u>TYPE</u>	<u>GALS/SX</u>	<u>PPG</u>	<u>FT<sup>3</sup>/SX</u>
<u>LEAD</u> 0-1700'	170 SX	1700'	35/65 PozC + 6% D20 + 5% D44 + 1/4# D29	11.84	12.4	2.13
<u>TAIL</u> 1700-2000'	100 sx	300'	Class "C" Neat	6.32	14.8	1.32