

STRAWBERRY 7 FED COM #2
DRILLING PLAN
PAGE 4

8. Logging, Testing and Coring Program

- A. Drill stem tests may be run on potential pay interval.
- B. The open hole electrical logging program will be as follows.
 - 1) DLL/MSFL/GR from total depth to base of intermediate casing.
 - 2) CNL/LDT/GR from total depth to base of intermediate casing with CNL/GR to surface.
- C. No coring program is planned.
- D. Additional testing will be initiated subsequent to setting the 5 1/2" production casing. Specific intervals will be targeted based on log evaluation, geological sample shows and drill stem tests.

9. Abnormal Pressures, Temperatures and Potential Hazards

No abnormal pressures or temperatures are foreseen. The anticipated bottom hole temperature at total depth is 170 degrees and maximum bottom hole pressure is 5500 psi. No Hydrogen sulfide or other hazardous gases or fluids have been encountered, reported or are known to exist at this depth in this area. No major loss circulation intervals have been encountered in adjacent wells.

10. Anticipated Starting Date and Duration of Operations

Road and location preparation will not be undertaken until approval has been received from the BLM. If approved, this well will be drilled as part of a development project. The anticipated spud date for the project is in June 2002. The drilling operation should require approximately 45 days. If the well is deemed productive, completion operations will require, at minimum, an additional 30 days of testing to ascertain whether permanent production facilities will be constructed.