

Operator Ready Oil & Gas Mngt.

Well Will Federal #14

Unit P Section 14 Township 2c Range 28

API # 30-015-02398

TOPS

Salade ~ 450'

Base salt ~ 650'

Yates ~ 775'

← 60' Surface Plug.

- * Contact OCD 24 hrs. prior to any work done.
- * Salt gel mud consisting of 10# brine with 25# of gel per barrel must be placed between each plug.
- * Install dry hole marker as per Rule 202.B.2
- * Plugs are to be set from point indicated up.
- * Plugs must not be less than 100' or 25 Sacks of cement, whichever is greater, unless specifically indicated.
- * Shoe and stub plugs will be 50' above and below shoe or stub and tagged.
- * Surface plug will be from 0' - 60'
- * Where plugs are required, cement must be placed inside and outside of all casing string(s) in the correct footage or sacks required, if no cement exists.
- * Plugs to be tagged will be indicated.

2
0

No casing Records.
Procedure may
change.

← 450' Cement Plug Inside + Outside casing. Top Salt Plug. TAG

← Cement Plug from TD - 650' - Shoe Plug / Base Salt Plug. TAG

MS