

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)



1. oil well ☒ gas well ☐ other ☐
2. NAME OF OPERATOR
Perry R. Bass
3. ADDRESS OF OPERATOR
P. O. Box 2760, Midland, Texas 79702
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1656' FSL & 1972' FWL
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐

SUBSEQUENT REPORT OF:

(other) Perforate & Acidize Strawn [X]



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

MIRUPU. Pull tbgs. & Pkr. Set Baker K-1 cmt retainer @ 11276'. Squeeze perfs w/125 sx Class "H" w/.75% CF-9/sx and tail w/ 75sx Class "H" w/2% WR-2. Both mixed 1.18 ft /sx & 15.6 ppg. POH. RIH w/ packer and test casing to 500# and POH. Found csg bowl leaking @ 3202'. Set Baker Model K-1 cmt retainer @ 3119'. Squeeze casing bowl w/ 75sx Class "H" w/ 75% CF-9/sx and tail w/ 85 sx Class "C" w/ 1% CaCl. Class "H" mixed @ 1.18 ft /sx & 15.6 ppg. Class "C" mixed @ 1.32 ft /sx & 14.8 ppg. Drilled out cmt & retainer to 3285'. Test csg to 700 psi. O.K. Continue to drill deep cmt. Drill cmt & Retainer from 11,220'-11,388'. Test csg. O.K. POH. Perf 11359'-11375' w/ 17 shots. Attempt acidize. Perfs would not take acid. Spot acid across perfs. Attempt to acidize. Perfs would not take acid. POH. Re-Perf interval 11,364'- 11,375' w/ 11 shots. Acidize w/ 4000 gals 20% HCl. Swab. Install artificial lift equipment. Well on pump. Perfs. 11,359'-11,375'. (28 holes)

Subsurface Safety Valve: Manu. and Type

Set @ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED R.C. Houtchens TITLE Sr. Prod. Clerk DATE 11-8-83

ACCEPTED FOR RECORD (This space for Federal or State office use)

APPROVED BY
CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

MAY 8 1984

Carlisle

*See Instructions on Reverse Side

ROSEMBO, NEW MEXICO

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between, and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.