

1. Contact the appropriate BLM office at least 24 hours prior to the scheduled test.

1

NOTE: A BLM technician must be present to witness all casing integrity tests.

2. A retrievable bridge plug or packer shall be set a maximum of 50 feet above any open perforations.

3. All downhole production equipment (tubing, rods, etc.) must be removed from the casing if they are not isolated by a packer.

4. The casing must be filled with fluid and pressure tested to 500 psi. Furthermore, the casing must be capable of holding this pressure for at least 15 minutes with a 10% allowable leak-off (i.e. 450 psi).

5. The operator must submit a subsequent report of test on Sundry Notices (Form 3160-5, formerly 9-331) to be accepted for record.

NOTE: Wells that successfully pass the casing integrity test will be approved for Temporary Abandonment status for 12 months provided that the operator submits a subsequent Sundry Notice.