BURTON FLAT UNIT WELL NO. 7

MUD PROGRAM

,

Surface:	<u>0 - 600'</u> Fresh water gel/lime slurry
Intermediate:	600' - 3000' Fresh water with L.C.M. for seepage
Production:	3000' - T.D. Fresh water and lime to 8500'. At 8,500' mud up with a fresh water low solids benex system (Wt. 8.9 to 9.2#/Gal.). At 10,000' increase weight to 9.7#/Gal. Adjust weight and viscosity as required to T.D. Reduce water loss to 5 cc before drilling Morrow.

