

AVALON HILLS NO. 2

MUD PROGRAM

Surface:                   0 - 600'  
                            Fresh water gel/lime slurry

Intermediate:           600 - 3000'  
                            Fresh water with L.C.M. for seepage

Production:             3000' - T.D.  
                            Fresh water and lime to 8500'.  
                            At 8500' mud up with a fresh water low solids  
                            Benex system (Wt. 8.9 to 9.2#/Gal.)  
                            At 10,000' increase weight to 9.7#/Gal.  
                            Adjust weight and viscosity as required to T.D.  
                            Reduce water loss to 5 cc before drilling Morrow.