

FASKEN-FEDERAL WELL NO. 2

MUD PROGRAM

Surface:	<u>0 - 500'</u> Fresh water gel/lime slurry
Intermediate:	<u>600 - 2100'</u> Fresh water with L.C.M. for seepage if required.
Production:	<u>2100' - T.D.</u> Fresh water to 7500'. At 7500' mud up with low solids, non-dispersed fresh water system. Weight and viscosity will be adjusted to contain the formation fluids. The water loss will be decreased to 5 c.c. or less before drilling the Morrow.