

Special Surface Equipment Recommended: Install prior to 8,900',
Mud and Gas Flowline Separator, Drilling Head, Degasser, Adjustable
Choke, Flow Sensor and Pit Volume Totalizer.