

FASKEN-FEDERAL WELL NO. 3

MUD PROGRAM

Surface: 0 - 500'
Fresh water gel/lime slurry

Intermediate: 600 - 2100'
Fresh water with L.C.M. for seepage if
required.

Production: 2100' - T.D.
Fresh water to 7500'. At 7500' mud up with
low solids, non-dispersed fresh water system.
Weight and viscosity will be adjusted to con-
tain the formation fluids. The water loss
will be decreased to 5 c.c. or less before
drilling the Morrow.