

Application for Permit to Drill Loafer Draw "B" No. 1

Page No. 3

October 31, 1975

3. Flow line sensor.

4. Degasser.

Also, prior to drilling out from under the 9-5/8", the BOP's and related control equipment will be pressure tested to rated working pressure by an independent testing company.

The well will be drilled in accordance with USGS requirements stated in Order No. 30 CFR 221.24, 221.36 and 221.37.

Please contact me at the above address if further information is needed to evaluate this project.

Yours very truly,



E. Y. Wilder
Region Operations Manager
Southwest Region
E & P Division

EYW/lrs

Attachments

RECEIVED
NOV 3 1975
U. S. GEOLOGICAL SURVEY
ARTESIA, NEW MEXICO