

Sam 3-

632-98.6
Nerman Smith
AVALON FED. #1 N 1-21-26

Their top atoka 10812'
Mark 10639

5 1/2" CSG. 17-20# TOP OF 20" 10736 K.B.
K.B. MEAS. 16'
P.B.T.D. 11100'
2 7/8" TBG. N-80 6.50# 8RD. EUE.
PERFORATIONS FROM: 10418-22 ATOKA FORMATION
10724-30, 10842-876, 10976-85, 10988-98 MORROW FORMATION

PROCEDURE TO PULL VAN GUNN & RUN PKR.

1. M.I.R.U. MENNER WELL SERVICE. BLOW WELL DOWN.
2. R.U. ROWLAND TRUCKING KILL TRUCK & PUMP 30 BBLs METHANOL DOWN 2 7/8" TBG. AND 30 TO 40 BBLs. 4% KCL WATER TO KILL WELL.
3. N.D. W/H, N.U.B.O.P.E.
4. PUMP 4% KCL WTR. DOWN ANNULUS BEFORE UNSEATING HALLIBURTON PERMA-LATCH PKR. TOTAL CAPACITY 163 BBLs.
5. T.O.H. W/2 7/8" TBG. & HALLIBURTON PERMA LATCH PKR. & HALLIBURTON VAN GUNN'S. TALLYING OUT.
6. P/U B.F.C. ON/OFF TOOL & 8' 2 7/8" SUB., 2 7/8" SLIDING SLEEVE & S.I.H. W/2 7/8" TBG. W/S/S/OPEN RUN APPROX. 9 JTS. 2 7/8" TBG. P/U. 2 7/8" X 5 1/2" FULL BORE ISOLATION PKR. & "F" NIPPLE I.D. 2.31. SPACE TBG. OUT TO SET PKR. @ 10448 K.B. P/U & RUN 1 JT. 2 7/8" TBG. ON TOP OF "F" NIPPLE. P/U SLIDING SLEEVE & RUN BAL OF 2 7/8" TBG. TO SURFACE.
7. STING INTO LOCK-SET PKR. @ 10736 K.B. & SET ISOLATION PKR., LOCATED @ 10448' K.B. N.D.B.O.P.E., N.U.W.H.
8. R.U. PRO WEST WIRELINE SERVICE & RUN PLUG DOWN 2 7/8" TBG. & SET PLUG IN "F" NIPPLE ON TOP OF ISOLATION PKR. AFTER SETTING PLUG. OPEN TOP SLIDING SLEEVE, LOCATED APPROX. @ 10415.5', R.D. PRO WEST WIRELINE SER.
9. R.U. TO SWABB 2 7/8" TBG. BY SWABBING ON THE TOP PREF'S 10418-22 SWABB WELL ON, FLOW WELL MAKING SURE WELL IS FREE OF WATER.
10. W/TOP ZONE DRY, R.U. PRO WEST WIRELINE SER. ON W/H W/LUBRICATOR. RUN IN 2 7/8" TBG., CLOSE SLIDING SLEEVE & REMOVE PLUG FROM "F" NIPPLE ON TOP OF ISOLATION PKR. & PRODUCE THE TOP ZONE UP ANNULUS AT THIS TIME. P.O.O.H. W/PLUG. R.D. PRO WEST WIRELINE SER.
11. R.U. & SWABB MIDDLE ZONE 10724-30' SWABB WELL ON & FLOW WELL 24/72 HRS. UNTIL WELL F/B. NO WATER. R.D. SWABB.
12. R.U. PRO WEST WIRELINE SER. W/LUBRICATOR R.I. 2 7/8" TBG. CLOSE BOTTOM SLIDING SLEEVE LOCATED APPROX. 10721' K.B. REMOVE PLUG IN LOCK-SET PKR. LOCATED @ 10736', P.O.O.H. W/PLUG. R.D. PRO WEST WIRELINE SER.
13. R.U. & SWABB BOTTOM "MORROW ZONE" ON W/BOTTOM ZONE FLOWING R.U. PRO WEST WIRELINE SER. W/LUBRICATOR R.I. 2 7/8" TBG. TO BOTTOM SLIDING SLEEVE & OPEN BOTTOM SLEEVE. P.O.O.H. W/WIRELINE. R.D. PRO WEST WIRELINE SER.
14. PUT WELL ON LINE. R.D. MENNER WELL SERVICE & MOVE OFF.