

LONE TREE WELL NO. 1

MUD PROGRAM

Surface:

0 - 600'

Fresh water gel/lime slurry

Intermediate:

600 - 3000'

Fresh water with LCM for seepage
if required.

Production:

3000 - TD

Fresh water to 7500'. At 7500' mud
up with low solids, non-dispersed
fresh water system.

Weight and viscosity will be ad-
justed to contain the formation
fluids.

The water loss will be decreased
to 5 cc or less before drilling
the Morrow.