

1. Ram-type blowout preventors and related control equipment shall be tested with the drilling fluid in use to the rated pressure of the stack assembly, with the exception of the Hydril which shall be tested to 70% of the rated working pressure - 10 minutes per test. They shall be tested:

- a. When installed and prior to drilling out after each string of casing is set
- b. Not less than once each fourteen days from each of the control stations
- c. Following repairs that require disconnecting a pressure seal in the assembly

2. When drillpipe is in use, pipe rams shall be actuated to test proper functioning daily. The Hydril shall be actuated on the drillpipe once each fourteen days.

3. A blowout prevention drill shall be conducted every fourteen days for each drilling crew.

