6. <u>CIRCULATING MEDIUM:</u>

Surface to 10,600 feet: We plan to clean out to 7952' with new mud and drill to a new TD of 10,600' with new drilling mud. 2

7. AUXILLARY EQUIPMENT:

None required.

8. TESTING, LOGGING, AND CORING PROGRAM:

Electric logging is planned.

9. ABNORMAL PRESSURES, TEMPERATURES, OR HYDROGEN SULFIDE GAS:

None anticipated.

10. ANTICIPATED STARING DATE:

It is planned that operations will commence on or before June 15, 1988, with drilling and completion operations lasting about 15 days.