

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals

**SUBMIT IN TRIPLICATE**

1. Type of Well

☐ Oil Well ☒ Gas Well ☒ Other Plugback to Strawn

2. Name of Operator

YATES PETROLEUM CORPORATION (505) 748-1471

3. Address and Telephone No.

105 South 4th St., Artesia, NM 88210

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Unit C, 330' FNL & 2310' FWL, Sec. 14-T21S-R22E

5. Lease Designation and Serial No.

NM 9531-A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Hilliard LE Federal #1

9. API Well No.

30-015-22909

10. Field and Pool, or Exploratory Area

Undesignated Strawn

11. County or Parish, State

Eddy, NM

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice


TYPE OF ACTION

- ☐ Abandonment  
☐ Recompletion  
☒ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☐ Other  
☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

2-13-93. Dug pit. Set tanks. Installed SV in Guiberson 1.81" on/off tool @ 8838'. Tested 2-7/8" tubing to 2500#. Got off on/off tool. POH. WIH w/packer set packer above perfs 8692-8714'. Swabbed Morrow.  
2-19-93. Set CIBP at 8630' w/35' cement on top. Perforated Strawn 7819-7826' w/16 - .42" holes (2 SPF) as follows: 7819, 20, 21, 22, 23, 24, 25 and 7826'. Acidized perfs 7819-7826' w/1500g. 7 1/2% Morflo with N2 + ball sealers.  
2-23-93. Swabbed dry. Installed 1/4" positive choke. FP 30# after 2 hrs. Rigged down and cleaned location.



14. I hereby certify that the foregoing is true and correct

Signed David R. Glass

Title Production Supervisor

Date 3-12-93

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any: