

Application for Drilling

Pogo Producing Company - Federal ~~XX~~ No. 1

Page 2

7. The rig will be equipped with safety devices such as kelly cock, drill pipe float, full opening stabbing valve, inside drill pipe BOP, etc. Operational test will be run periodically and results noted on tour sheets.
8. One drill stem test is planned at depth to be determined. Compensated neutron density with gamma ray log is to be run at TD.
9. No abnormal pressures or temperatures or potential hazards are expected to be encountered.
10. Anticipated starting date is expected to be October 25, 1979, with completion of operations expected to be on or about November 25, 1979.