

7. A kelly cock will be installed and maintained in operable condition.
8. After setting the 8-5/8" casing string and before drilling into the Wolfcamp formation, the blowout preventers and related control equipment shall be pressure tested to rated working pressures by an independent service company. Any equipment failing to test satisfactorily shall be repaired or replaced. This office should be notified in sufficient time for a representative to witness the tests and shall be furnished a copy of the pressure test report.
9. Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be installed and operating before drilling into the Wolfcamp formation and used until production casing is run and cemented. Monitoring equipment shall consist of the following:
 - (1) A recording pit level indicator to determine pit volume gains and losses.
 - (2) A mud volume measuring device for accurately determining mud volume necessary to fill the hole on trips.
 - (3) A flow sensor on the flow-line to warn of any abnormal mud returns from the well.
10. Notify the Survey by telephone 24 hours prior to spudding well.
11. Notify the Survey in sufficient time to witness the cementing of the 8-5/8" and 5-1/2" casing.
12. Cement behind the 11-3/4", 8-5/8", and 5-1/2" casing must be circulated.
13. It is required that a Gamma-Ray-Neutron Log be run in open hole from the base of Salado to the surface at a speed not to exceed 30 feet per minute.
14. Special Stipulations:
 - (1) Utilize caliche pit in SW/4 SW/4 Sec. 33, T.20S., R.30E.
 - (2) Oblong reserve pits in order to keep them out of draw.
 - (3) Install culverts where access roads cross large draws.