

DEVON ENERGY CORPORATION
Interoffice Correspondence

12/30/97 7:44 AM

TO: Rick Clark

FROM: W.M. Frank

RE: Recompletion Prognosis
Pure 11 "P" Federal #2 (DEC 50% WI)
1270' FSL & 810' FEL
Section 11-T21S-R25E
Eddy County, New Mexico

Well Data: Elevation - 3316' R.K.B.
3297' GL

TD - 10,552' Logger

PBTD - 10,464' Logger

Perforations - 10,216 - 219, 10,255 - 267' (Morrow)

Casing - 13-3/8" 54.5 & 61# K-55 @ 450', Top job cmt to surface
- 8-5/8" @ 3500', Cmt to surface
- 5-1/2" 17#, L-80 @ 10,552' w/1050 sx TOC - 7240'
(CBL)
- DV tool @ 5501', Cmt w/950 sxs TOC @ 1100' (Temp Survey)

Packer - with On/Off tool. @ 10,141'
2 3/8", 4.7#, N-80, 8rd tubing
Capacity - 0.0039 bpf
Displacement - 0.00171 bpf
Burst - 11200 psig new, 8400 psig @ 75%

Procedure

1. MIRU pump truck. RU on tubing annulus and pressure test casing to 1,000 psig f/15 min. If test is OK then go to step 2. If test is no good then a supplemental procedure will be issued.