

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

OIL CONS COMMISSION
Drawer DD
Artesia, NM 88210

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

RECEIVED

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

BASS ENTERPRISES PRODUCTION CO.

3. Address and Telephone No.

P. O. BOX 2760 MIDLAND, TEXAS 79702-2760

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SW/4 of NE/4 of Section 18, T21S, R29E

1980 N 190E

5. Lease Designation and Serial No.

NMLC-062573

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

BIG EDDY UNIT

8. Well Name and No.

BIG EDDY UNIT #84

9. API Well No.

30-015-23968

10. Field and Pool, or Exploratory Area

GOLDEN LANE (WOLFCAMP)

11. County or Parish, State

EDDY COUNTY, NEW MEXICO

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other TEMPORARILY ABANDON

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

BASS ENTERPRISES PRODUCTION CO. PROPOSES TO ABANDON THE PRESENT ZONE, PERFORM A CASING INTEGRITY TEST AND TEMPORARILY ABANDON THE WELLBORE FOR APPROXIMATELY 12 MONTHS. A CAST IRON BRIDGE PLUG WILL BE SET AT 9910' AND 35 sx OF CEMENT DUMPED ON TOP. THIS WELL HAS BEEN PERMITTED AS A SALT WATER DISPOSAL WELL. THE ABANDONMENT WORK WILL BEGIN UPON BUREAU OF LAND MANAGEMENT APPROVAL. THE CONVERSION WORK WILL BEGIN IN MID-1995.

CERTIFIED #Z 112 327 574 - WHF:PGO

14. I hereby certify that the foregoing is true and correct

Signed Keith E. Bucy KEITH E. BUCY Title DIVISION PRODUCTION SUPT.

Date 8/31/94

(This space for Federal or State office use)

Approved by (ORIG. SGP.) JOE G. LARA PETROLEUM ENGINEER

Date 9/29/94

Conditions of approval, if any: See attached.

BIG EDDY UNIT NO. 84

LOCATION; 1980' FNL & 1980' FEL, SEC 18, T21S, R29E
API NO: 30-015-23968
ELEVATIONS; GL 3308' KB 3326'
SPUD DATE; 11/9/81 COMP. DATE; 3/15/83

BASS ENTERPRISES
GOLDEN LANE (WOLFCAMP)
EDDY COUNTY, N.M.
DATE: 8-31-94 WHF



11-3/4" 43#/FT. H-40 ST&C CSA 758'.
CMTD W/450 SX PACESETTER LITE
200 SX CLASS 'C'. CMT CIRC. TO
SURFACE. HOLE SIZE 15'.

8-5/8" 28#/FT S-80 ST&C CSA 3023'.
CMTD W/3800 SX PACESETTER LITE.
CMT CIRC. TO SURFACE. HOLE SIZE 11'

SPOTTED CMT PLUG, 50 SX, BTM OF CMT
@ 12125'. TAGGED TOP OF CMT @ 11881'.

5-1/2" 17#/FT N-80 & S85 LT&C CSA 12725.
CMTD W/200 SX PACESETTER LITE & 500
SX CLASS H. HOLE SIZE 7-7/8".

WELLBORE INFORMATION

TBG: 2-3/8" 4.7#/FT. BRD EUE N-80
ABC MOD TUBING

CALC. TOC @ 8045'

PKR: OTIS MODEL MH-2 @ 9830'

PERFS: 10041'-10044' (4 SHOTS)


PERFS: 10134'-10148' (18 SHOTS)

PERFS: 11987'-11972' (8 SHOTS)

PKR: OTIS MODEL "WB" @ 12175'

PERFS: 12230'-12423' (8 SHOTS)

TD 12725'



BIG EDDY UNIT NO. 84

LOCATION; 1980' FNL & 1980' FEL, SEC 18, T21S, R29E
API NO: 30-015-23968
ELEVATIONS; GL 3308' KB 3326'
SPUD DATE; 11/9/81 COMP. DATE; 3/15/83

BASS ENTERPRISES
GOLDEN LANE (WOLFCAMP)
EDDY COUNTY, N.M.
DATE: 8-31-94 WHF




11-3/4" 43#/FT. H-40 ST&C CSA 758'.
CMTD W/450 SX PACESETTER LITE
200 SX CLASS 'C'. CMT CIRC. TO
SURFACE. HOLE SIZE 15'.

8-5/8" 28#/FT S-80 ST&C CSA 3023'.
CMTD W/3800 SX PACESETTER LITE.
CMT CIRC. TO SURFACE. HOLE SIZE 11'

SPOTTED CMT PLUG, 50 SX, BTM OF CMT
@ 12125'. TAGGED TOP OF CMT @ 11881'.

5-1/2" 17#/FT N-80 & S85 LT&C CSA 12725.
CMTD W/200 SX PACESETTER LITE & 500
SX CLASS H. HOLE SIZE 7-7/8'.



WELLBORE INFORMATION

CALC. TOC @ 8045'

CIBP SET @ 9910' W/ 35' CMT

PKR: OTIS MODEL MH-2 @ 9930'

PERFS: 10041'-10044' (4 SHOTS)

PERFS: 10134'-10149' (18 SHOTS)

PERFS: 11887'-11892' (8 SHOTS)

PKR: OTIS MODEL 'WB' @ 12175'

PERFS: 12230'-12423' (8 SHOTS)

TD 12725'

BUREAU OF LAND MANAGEMENT
CARLSBAD RESOURCE AREA

Temporary Abandonment of Wells on Federal Lands

Conditions of Approval

According to 43 CFR 3162.3-4-c, " No well may be temporarily abandoned for more than 30 days without the prior approval of the authorized officer".

Temporary Abandonment (TA) status approval requires a successful casing integrity test as follows:

1. Contact the appropriate BLM office at least 24 hours prior to the scheduled Casing Integrity Test. For wells in Eddy County call (505) 887-6544 ; for wells in Lea County call (505) 393-3612.
2. A bridge plug or packer shall be set at a maximum of 50 feet above any open perforations or open hole.
3. All downhole production/injection equipment (tubing, rods, etc.) shall be removed from the casing if they are not isolated by a packer.
4. The production casing shall be filled with corrosion inhibited fluid and pressure tested to 500 psi. The casing shall be capable of holding this pressure for at least 30 minutes with a 10% allowable leak-off.

Wells that successfully pass the casing integrity test will be approved for Temporary Abandonment (TA) status for 12 months provided that the operator:

1. Submits a subsequent Sundry Notice requesting TA approval,
2. Attaches a clear copy or the original of the pressure test chart,
3. And attaches a detailed justification why the well should not be plugged and abandoned.

The TA status could be extended without another casing integrity test provided there was no leak-off during the test.

If the well does not pass the casing integrity test, then the operator shall within 30 days submit to BLM for approval one of the following:

1. A procedure to repair the casing so that a TA approval can be granted.
2. A procedure to plug and abandon the well.