

8. Testing, logging, and completion programs:

- A. Logging: 600'-3000' FDC-CAL-GR/DLL-MSFL  
3000'-TD FDC-CNL-CAL-GR/DLL-MSFL
- B. Mud logger from 200'-TD.
- C. Completion-formation: Morrow (11050'+ - 11200'+). Proposed completion procedure: spot acid across Pay Zone. Run GR-CCL and perforate. Acidize with 6000 gallons 7-1/2% HCL.
- D. Production method: Run packer on 2-7/8" tubing and set above Morrow perforations. Produce Morrow gas up the tubing.

9. Abnormal pressure or other possible hazards:

- A. No abnormal pressure is anticipated.
- B. No H<sub>2</sub>S problem is expected.

10. It is anticipated that the drilling and completion operations will begin about January 15, 1982, and be finished in approximately 14 weeks.