

8. Testing, logging, and completion programs:

A. Logging:                      600'-3000' FDC-CAL-GR/DLL-MSFL  
                                    3000'-TD      FDC-CNL-CAL-GR/DLL-MSFL

B. Mud logger from 200'-TD.

C. Completion-formation: Morrow (11050'+ - 11200'+). Proposed completion procedure: spot acid across Pay Zone. Run GR-CCL and perforate. Acidize with 6000 gallons 7-1/2% HCL.

D. Production method:      Run packer on 2-7/8" tubing and set above Morrow perforations. Produce Morrow gas up the tubing.

9. Abnormal pressure or other possible hazards:

A. No abnormal pressure is anticipated.

B. No H<sub>2</sub>S problem is expected.

10. It is anticipated that the drilling and completion operations will begin about January 15, 1982, and be finished in approximately 14 weeks.