

Tuesday A Federal No. 1
Pg 3

3572'-3590' for total of 38 perfs. POOH. Set treating
pk at 3500'. Load backside w/TFW and pressure
up to 500 psi. Acidize Upper Delaware zone w/1512
gals 7½% HCL-NE-FE acid inhibited for 24 hrs.
at 3-5 BPM dropping 3 each ⅞" RCN ballsealers 1.35g
after every two lbs acid pmpd. Total of 51 ballsealers.
Flush w/25 BTFW w/1:1000 Cla-Sta. Shut-in for 1 hr.
Swab well. If zone is non-commercial release treating
pk at 3500' & POOH. Set retained at 3540'. Load backside
w/TFW & pressure to 500 psi. Cement squeeze Delaware
Zone B interval w/50 sacks class "C" cement. Flush to
retained w/21 BTFW. Spot 2 sacks cement on top retained
& reverse circulate out excess slurry. POOH. Tuesday
A Federal No. 1 will be temporarily abandoned if no
uphole productive intervals are found.