

8. Logging & Testing Program: (See Exhibit E)

Dual Induction, Density, Caliper, Neutron, Gamma Ray, 6000'-T.D.

DST's: 1 DST planned in the Cisco

Mud Logging:

Mud logger to be rigged up and running when drilling below intermediate casing. Sample collection and other specific instructions to come from wellsite geologist.

9. No abnormal pressures or temperatures are anticipated. H₂S possible in San Andres (1079'). See H₂S Contingency Plan.

10. Anticipated starting date: As soon as possible.