

7. CORING, LOGGING & TESTING PROGRAM

Open hole, possible 60' core from Delaware Sand.

8. * Full suite of E-logs shall be run. (SJS)
ABNORMAL CONDITIONS:

A. The expected bottom hole pressure is 1400 psi, no abnormal temperatures are expected.

B. 2% H₂S is expected from the Delaware Sand, precautions will be taken prior to zone entry.