

7. CORING, LOGGING & TESTING PROGRAM

DLL, CNL, FDC logs will be run.

8. ABNORMAL CONDITIONS:

- A. The expected bottom hole pressure is 1400 psi, no abnormal temperatures are expected.
- B. 2% H<sub>2</sub>S is expected from the Delaware Sand, precautions will be taken prior to zone entry.