- 3. LOCATION OF WATER WELLS IN A ONE-MILE RADIUS
- A. Water wells None known.
- B. Disposal wells None known.
- 4. If, upon completion, the well is a producer, Strata Production Company, will furnish maps or plats showing On Well Pad facilites and Off Well Pad facilities (if needed) on a Sundry Notice before construction of these facilities starts.
- 5. LOCATION AND TYPE OF WATER SUPPLY

Water will be purchased locally from a private source and trucked over the access roads.

6. SOURCE OF CONSTRUCTION MATERIALS

If needed, construction materials will be obtained from the drill site's excavations or from a local source. These materials will be transported over the access route as shown on Exhibit "A".

- 7. METHODS FOR HANDLING WASTE DISPOSAL
  - A. 1. Drill cuttings will be disposed of in the reserve pit.
    - 2. Trash, waste paper, and garbage will either be contained in a fenced trash trailer or in a trash pit, fenced with mesh wire to prevent windscattering during storage. When the rig moved out, all trash and debris left at the site will be contained to prevent scattering and will be buried at least 36" deep within a reasonable period of time.
    - Salts remaining after completion of the well will be picked up by the supplier, including broken sacks.
    - 4. Sewage from trailer houses will drain into holes with minimum depth of 10'00". These holes will be covered during drilling and backfilled upon completion. A "porta John" will be provided for