

- Electric Logs:
 - Dual Induction Laterolog
 - Neutron Porosity Log
 - Gamma Ray/Caliper Log

- Coring:
 - Some sidewall coring will be done if necessary.

9. Abnormal Pressures, Temperatures, or other Hazards:

- Lost circulation is anticipated in the surface interval of the hole, and possibly in the Capitan Reef interval.

10. Anticipated Starting Date: As soon as possible.

- Expected Duration of Operations.

- Drilling - 10 days

- Completion - 15 days