

7. CORING, LOGGING & TESTING PROGRAM

DLL, CNL, FDC logs will be run.

8. ABNORMAL CONDITIONS:

- A. The expected bottom hole pressure is 1400 psi, no abnormal temperatures are expected.
- B. 2% H²S is expected from the Delaware Sand, precautions will be taken prior to zone entry.