

11. The testing, logging, and coring programs are as follows:

D.S.T.'s or cores: None

Logs: DIL/GR/Cal TD - 3500'

LDT/CNL/GR/Cal TD - 3500'

CNL/GR 3500' to surface

Mud Log TD - 3500'

Special Tests: None

12. Anticipate no abnormal pressures or temperatures to be encountered or any other potential hazards such as Hydrogen Sulfide Gas. Low risk H₂S equipment will be used.
13. The anticipated starting date is immediately upon approval with duration of operations for approximately 30 days thereafter.
14. Water Supply: Hauled
15. Caliche for road and pad construction to be obtained from Federal pit in Sec. 11 or on site location.