Chi Operating, Inc. Winchester Federal, Well No. 2 Page 2

# LOCATION OF EXISTING AND/OR PROPOSED FACILITIES;

- A. There are gas production facilities on the lease at the Winchester Fed., Well #1, 1980' FNL & 660' FEL Sec. 4-T20S-R28E.
- B. If the well proves to be commercial, the necessary production facilities, gas separation-process equipment and tank battery will be installed on the drilling pad.

# 5. LOCATION AND TYPE OF WATER SUPPLY:

A. It is planned to drill the proposed well with fresh water that will be obtained from private or commercial sources and will be transported over the existing and proposed access roads or a fast line beside existing roads may be used.

#### 6. SOURCE OF CONSTRUCTION MATERIALS:

A. Caliche for surfacing the proposed access road and well site pad will be obtained from a pit on the location or from a federal pit in the SE4, Sec. 12-T20S-R27E. The topsoil from the location will be stockpiled near the location for future rehabilitation use. No surface materials will be disturbed except those necessary for actual grading and leveling of the drill site and access road.

### 7. METHODS OF HANDLING WASTE DISPOSAL:

- A. Drill cuttings will be disposed of in the reserve pits.
- B. Drilling fluids will be allowed to evaporate in the reserve pits until the pits are dry.
- C. All pits will be fenced with normal fencing materials to prevent livestock from entering the area.
- D. Water produced during operations will be collected in tanks until hauled to an approved disposal system, or a separate disposal application ill be submitted to the BLM for approval.
- E. Oil produced during operations will be stored in tanks until sold.
- F. Current laws and regulations pertaining to the disposal of human waste will be complied with.
- G. Trash, waste paper, garbage and junk will be buried in a separate trash pit and covered with a minimum of 24 inches of dirt. All waste material will be contained to prevent scattering by the wind.
- H. All trash and debris will be buried or removed from the well site within 30 days after finishing drilling and/or completion operations.

### 8. ANCILLARY FACILITIES:

A. None required.