

9. ABNORMAL CONDITIONS, PRESSURES, TEMPERATURES, & POTENTIAL HAZARDS:
No abnormal pressures or temperatures are anticipated. The estimated bottom hole temperature (BHT) at TD is 125 F and the estimated maximum bottom hole pressure (BHP) is about 2500 psi. No hydrogen sulphide (H₂S) or other hazardous fluids are known to exist at this depth in this area. Possible lost circulation zones in the Artesia Group, Capitan Reef, Delaware, and Bone Springs.
10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:
It is planned that operations will commence shortly after approval of this application, with drilling and completion operations lasting about 30 days. A decision as to design and installation of permanent facilities will be made after adequate testing of the well.