

6. EVALUATION PROGRAM:

Samples: Every 10' out from under surface casing.

Logging: CNL/LDT - TD to casing with CNL/GR 5" to surface; DLL/MSFL, TD to casing; LSS, TD to surface; possible intermediate logs 4000' to 1550' - CNL/LDT, DLL/MSFL.

Coring: As warranted.

DST's: As warranted

7. ABNORMAL CONDITIONS

No abnormal temperatures or pressures are anticipated. No H<sub>2</sub>S anticipated.

8. ANTICIPATED STARTING DATES

Plans are to drill this well before the end of the year. It should take approximately 55 days to drill the well with completion taking another 20 days.