

8. Testing, Logging and Coring Program:

Samples: Out from under surface casing to TD.

DST's: As warranted.

Coring: None anticipated.

Logging: Dual Induction Laterolog, Gamma Ray/Litho Density, Gamma Ray/Compensated Neutron with Caliper Log.

9. No abnormal pressures or temperatures are anticipated. No H<sub>2</sub>S is expected to be encountered during drilling operations. *BHP @ TD ~ 3488 psig.*

10. Anticipated starting date: As soon as possible after approval/*Duration: 30 days.*