

- B. Remaining drilling fluids will be allowed to evaporate in the reserve pit until the pit is dry enough for backfilling. In the event drilling fluids will not evaporate in a reasonable period of time, they will be transported by tank truck to a state approved disposal site.

Water produced during testing of the well will be disposed of in the reserve pit. Oil produced during the testing of the well will be stored in test tanks until sold and hauled from the site.

8. ANCILLARY FACILITIES

No camps or airstrips will be constructed.

9. WELL SITE LAYOUT

- A. Exhibit "C" is the H₂S Drilling Operations Plan.
- B. Exhibit "D" (Scale 1" = 50') shows the proposed well site layout.
- C. This exhibit indicates the proposed location of reserve pit, trash trailer and living facilities.
- D. Mud pits in the active circulation system will be steel pits.
- E. The reserve pit will be lined with a polyethylene liner. The pit liner will be a minimum of 2' over the reserve pit walls where the liner will be anchored down.
- F. The reserve pit will be fenced on three sides with four strands of barbed wire during drilling and completion operations. The fourth side will be fenced after drilling has been completed. If the well is a producer, the reserve pit fence will be torn down. The reserve pit and those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements.

10. PLANS FOR RESTORATION OF SURFACE

Rehabilitation of the location and reserve pit will start in a timely manner after all drilling operations cease. The type of reclamation will depend on whether the well is a producer or a dry hole.

However, in either event, the reserve pit will be allowed to dry properly, and fluid removed and disposed of in accordance with Article 7.8 as previously noted. The pit area will then be leveled and contoured to conform to the original and surrounding area. Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location pad and surface facilities. After the area has been shaped and contoured, top soil from the spoil pile (if any) will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.