Form 3160-3 (December 1990)

UNITED STATES SUBMIT IN TRIPLICATE 62 DEPARTMENT OF THE INTERIOR (See other instrum 1988)

う/ Form approved.	
,	

-	RIP	EAUC A	ND MANAGEMEN	П	सम्बद्धाः		·	DESIGNATION AND CUD	CY.
				<i>P</i> .		M 33210-28	54	DESIGNATION AND SER LC063246D for SHI	
			WIT TO DRILL	OR DE	EPEN			IAN, ALLOTTEE OR TRIE	
la TYPE OF WORK:	DRILL	\boxtimes	DEEPEN [J			N/A	GREEMENT NAME	
b. TYPE OF WELL:	GAS 57		. SINGLE	57	MULTIPLE		SW-2		
2 NAME OF OPERATO	WELL X	Other <u>Diec</u>	tona zone	\square	ZONE	<u> </u>	_	OR LEASE NAME, WELL	NO.
2 NAME OF OPERATO		RGY CORPO	RATION (NEVAD	DA)	101	37		ton Gas Comm. #3	20201
3. ADDRESS AND TEL	EPHONE NO.	· · · · · · · · · · · · · · · · · · ·					9.API W		
			2 1500, OKC, OK 7			1	30-01	SAND POOL, OR WILDCA	AT
4. LOCATION OF WELL At surface 2167' F			ccordance with any Sta n 31-21S-24E, Eddy C		nents)*		1	n Basin (Morrow)	
			-					T.,R.,M.,OR BLOCK AND	
At top proposed prod. z	one 660' FSL &	1650' FEL, Uni	t O, Section 31-21S-24	E, Eddy C	nty, NM			: Unit K, Section 31, : Unit O, Section 31,	
14.DISTANCE IN MILES AND	DIRECTION FROM N	AREST TOWN O	R POST OFFICE*	 	•		12. COU	NTY OR PARISH	13. STATE
24 miles NW of Carlsh	ad, NM						Edd	y County	New Mexic
15.DISTANCE FROM PROPOS	EĎ		16.NO. OF ACRES IN 1	LEASE			L	17.NO. OF ACRES	
LOCATION TO NEAREST PROPERTY OR LEASE LI	NE, FT.	660' at BHL	119.22 for SHL	and BHL		A AA	; * *	1	E SHL and BHL
(Also to nearest drig, unit line			19.PROPOSED DEPTH	ī				20.ROTARY OR C	
TO NEAREST WELL, DRII OR APPLIED FOR, ON TH		2035' at BHL	9,800' TVD / 1	10,420' MI	D			Rotary	
21.ELEVATIONS (Show whether	<u> </u>		<u></u> .L				22.	APPROX. DATE WORK V	VILL START*
GL 3906' at SHL							,	June, 1998	
23.		-	PROPOSED CASIN	G AND C	EMENTING	PROGRAM			
SIZE OF HOLE	GRADE, SIZE C	F CASING	WEIGHT PER F			SETTING DEI		QUANTITY	OF CEMENT
12 1/4"	K-55	9 5/8"	36			1,200'		500 sx Pozmix & 2	200 sx Class C
8 3/4"	J-55 / L-80	7"	23 / 26 / 29			10,420'		+/-1100 sx Class I	I
Devon Energy proposed depths assumed TVD of Programs to adhere to Drilling Program Surface Use and Opera Exhibits #1 = Blowout Exhibits #2 = Location Exhibits #3 = Road Mischibits #4 = Wells Wischibits #5 = Producti Exhibits #6 = Rotary Rischibits #7 = Casing Dischibits #7 = Casing Dischibits #7 = Casing Dischibits #6 = Rotary Rischibits #7 = Casing Dischibits #7 = Casing Dischibits #7 = Casing Dischibits #6 = Rotary Rischibits #7 = Casing Dischibits #7 = Casing Dischibits #7 = Casing Dischibits #6 = Rotary Rischibits #7 = Casing Dischibits #6 = Rotary Rischibits #7 = Casing Dischibits #6 = Rotary Rischibits #7 = Casing Dischibits #7 = Casing Dischibits #6 = Rotary Rischibits #6 = Rotary Rischibits #6 = Rotary Rischibits #6 = Rotary Rischibits #7 = Casing Dischibits #6 = Rotary Rischibits #7 = Casing Dischibits #6 = Rotary Rischibits #6 = Rotary Rischibits #7 = Casing Dischibits #6 = Rotary Rischibits #7 = Casing Dischibits #6 = Rotary Rischibits #6 = Rotary Rischibits #7 = Casing Dischibits #6 = Rotary Rischibits #6 =	anless otherwise quonshore oil and gasting Plan Prevention Equipand Elevation Platap and Topo Mapthin 1 Mile Radius on Facilities Platage Layout Proposition of the Company	ualified. If the is regulations a ment	well is deemed nonce re outlined in the follo the following the followin	ommercia owing exh The un and res portion Lease: Legal l Bond (BLM I	I, the well bo ibits and atta dersigned ac strictions con s thereof, as #: NM-LCO Description: Coverage: N Bond #: CO- data on pres	ore will be plu achments. eccepts all appl acerning opera described be 63246D Section 31-T (ationwide -1104	icable terms, ations conductors with the conductors and provided the conductors are conductors. The conductors are conductors are conductors are conductors are conductors are conductors are conductors.	conditions, stipulation ted on the leased land to t	egulations. Ins I or: 98 Loc ive zone. If
SIGNED Gar	dace R.	Yraho use)	Lm TITLI		ce R. Graha cering Techr		DATE	May 13, 1998	
PERMIT NO					_ APPRO	OVAL DAT	`E		
Application approval does n									
thereon. CONDITIONS OF APP									
			Monto	Assista	nt Field C	Office Man	ager,		
APPROVED BY	IG. SGD.) ARMAI	VDO A LOPEZ	TITLE _	Lands a	and Miner	als		ATE JUL 2	3 1998

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

See Instructions On Reverse Side

DISTRICT I P. O. Box 1980 Hobbs, NM 88241-1980

Artesia, NM 88211-0719

P. O. Drawer DD

DISTRICT III

1 API Number

En

² Pool Code

State of New Mexico Minerals, and Natural Resources ' EXHIBIT#

INDIAN BASIN (MORROW)

Form C-102 Revised 02-10-94

Instructions on back

OIL CONSERVATION DIVISION P. O. Box 2088 Santa Fe, New Mexico 87504-2088

3 Pool Name

Submit to the Appropriate District Office State Lease - 4 copies Fee Lease - 3 copies

1000 Rio Brazos Rd. Aztec, NM 87410 DISTRICT IV P. O. Box 2088

Santa Fe, NM 87507-2088 WELL LOCATION AND ACREAGE DEDICATION PLAT

AMENDED REPORT

3

3906'

County

EDDY

County **EDDY**

C

Well Number

• Elevation

East/West line

WEST

EAST

1998

1650

5 Property Name * Property Code WINSTON GAS COM 'OGRID No. 4 Operator Name DEVON ENERGY CORPORATION (NEVADA) 6137 "SURFACE LOCATION Lot Ida Feet from the North/South line Feet from the UL or lot no. Section Township Range 2167 SOUTH 21 SOUTH 24 EAST, N.M.P.M. K 31 "BOTTOM HOLE LOCATION IF DIFFERENT FROM SURFACE Lot Ida Feet from the North/South line Feet from the East/West line UL or lot no. Section Township Range 21 SOUTH 24 EAST, N.M.P.M. 660' SOUTH 12 Dedicated Acres 13 Joint or Infill 14 Consolidation Code 15 Order No. 3/20640 NO ALLOWABLE WELL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION Signature LŎCATION SURFACE 1998 2167' BOTTOM HOLE 650 660 JOB #58199


OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Candace Printed Name Candace R. Graham Title Engineering Tech. May 11, 1998

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.



51 NE


V.H.B.

3,000 psi Working Pressure

3 MWP

STACK REQUIREMENTS

No.	item		Min. I.D.	Min. Nominal
1	Flowline			
2	Fill up line			2*
3	Drilling nipple			
4	Annular preventer			
5	Two single or one dual hy operated rams	draulically		
6a	Drilling spool with 2" min 3" min choke line outlets			
6b	2" min. kill line and 3" m outlets in ram. (Alternate			
7	Valve	Gate 🗆 Plug 🗆	3-1/8"	
8	Gate valve—power opera	3-1/8"		
9	Line to choke manifold			3-
10	Valves	Gate □ Plug □	2-1/16"	
11	Check valve		2-1/16"	
12	Casing head			
13	Valve	Gate □ Plug □	1-13/16*	
14	Pressure gauge with nee			
15	Kill line to rig mud pump		2"	



OPTIONAL							
16 Flanged valve	1-13/16"						

CONTRACTOR'S OPTION TO FURNISH:

- All equipment and connections above bradenhead or casinghead. Working pressure of preventers to be 3,000 psi, minimum.
- Automatic accumulator (80 gatton, minimum) capable of closing BOP in 30 seconds or less and, holding them closed against full rated working pressure.
- 3.80P controls, to be located near drillers position.
- 4. Kelly equipped with Kelly cock.
- 5.Inside blowout prevventer or its equivalent on derrick floor at all times with proper threads to fit pipe being used.
- 6.Kelly saver-sub equipped with rubber casing protector at all times.
- 7.Plug type blowout preventer tester.
- Extra set pipe rams to fit drill pipe in use on location at all times.
- 9.Type RX ring gaskets in place of Type R.

MEC TO FURNISH:

- Bradenhead or casinghead and side valves.
- 2.Wear bushing, if required.

GENERAL NOTES:

- Deviations from this drawing may be made only with the express permission of MEC's Drifting Manager.
- 2.All connections, valves, fittings, piping, etc., subject to well or pump pressure must be flanged (suitable clamp connections acceptable) and have minimum working pressure equal to rated working pressure of preventers up through chore. Valves must be full opening and suitable for high pressure mud service.
- Controls to be of standard design and each marked, showing opening and closing position.
- 4. Chokes will be positioned so as not to hamper or delay changing of choke beans. Replaceable parts for adjustable choke, other bean sizes, retainers, and choke wrenches to be conveniently located for immediate use.
- All valves to be equipped with handwheels or handles ready for immediate use.
- 6. Choke lines must be suitably anchored.

- Handwheels and extensions to be connected and ready for use.
- Valves adjacent to drilling spool to be kept open. Use outside valves except for emergency.
- All seamless steel control piping (3000 pai working pressure) to have flexible joints to avoid stress. Hoses will be permitted.
- Casingheed connections shall not be used except in case of emergency.
- 11.Do not use kill line for routine fill-up operations.

Attachment to Exhibit #1 NOTES REGARDING BLOWOUT PREVENTORS

Devon Energy Corporation (Nevada) WINSTON GAS COMM. #3

SHL: 2167' FSL & 1998' FWL, Section K-31-T21S-R24E BHL: 660' FSL & 1650' FEL, Section O-31-T21S-R24E Eddy County, New Mexico

- 1. Drilling nipple will be constructed so it can be removed mechanically without the aid of a welder. The minimum internal diameter will equal BOP bore.
- 2. Wear ring will be properly installed in head.
- 3. Blowout preventor and all associated fittings will be in operable condition to withstand a minimum 3000 psi working pressure.
- 4. All fittings will be flanged.
- 5. A full bore safety valve tested to a minimum 3000 psi WP with proper thread connections will be available on the rotary rig floor at all times.
- 6. All choke lines will be anchored to prevent movement.
- 7. All BOP equipment will be equal to or larger in bore than the internal diameter of the last casing string.
- 8. Will maintain a kelly cock attached to the kelly.
- 9. Hand wheels and wrenches will be properly installed and tested for safe operation.
- 10. Hydraulic floor control for blowout preventor will be located as near in proximity to driller's controls as possible.
- 11. All BOP equipment will meet API standards and include a minimum 40 gallon accumulator having two independent means of power to initiate closing operation.

	1	3,000 MWP			5,000 MWP			10,000 MWP		
No.		I.D.	NOMINAL	RATING	I.D.	NOMINAL	RATING	1.0.	NOMINAL	RATING
1	Line from drilling spool		3-	3,000		3-	5,000		3.	10,000
2	Cross 3"x3"x3"x2"			3,000			5,000			
•	Cross 3"x3"x3"x3"									10,000
3	Valves(1) Gate □ Plug □(2)	3-1/8"		3,000	3-1/8*		5.000	3-1/8"		10,000
4	Valve Gate □ Plug □(2)	1-13/16"		3,000	1-13/16"		5,000	1-13/16"		10,000
42	Valves(1)	2-1/16"		3,000	2-1/16"		5,000	3-1/8"		10,000
5	Pressure Gauge			3,000			5,000			10,000
6	Valves Gate □ (2)	3-1/8*		3,000	3-1/8"	,	5,000	3-1/8"		10,000
7	Adjustable Choke(3)	2"		3,000	2*		5,000	2-		10,000
8	Adjustable Choke	1"		3,000	1.		5,000	2-	1	10,000
9	Line		3-	3,000		3*	5,000		3.	10,000
10	Line		2*	3,000		2.	5.000		3.	10,000
11	Valves Gate ☐ Plug ☐(2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8*		10,000
12	Lines		3*	1,000		3.	1,000		3*	2.000
13	Lines		3-	1,000		3-	1,000		3*	2,000
14	Remote reading compound standploe pressure dauge			3.000			5,000			10.000

MINIMUM REQUIREMENTS

Plug (2) (1) Only one required in Class 3M.

Gate []

standpipe pressure gauge

Gas Separator

15

16

17

Line

Valves

- (2) Gale valves only shall be used for Class 10M.
- (3) Remote operated hydraulic choke required on 5,000 psi and 10,000 psi for drilling.

3-1/8"

EQUIPMENT SPECIFICATIONS AND INSTALLATION INSTRUCTIONS

1,000

3.000

3-1/8"

2'x5'

4"

1,000

5,000

3-1/8"

2'x5'

2,000

10,000

- 1. All connections in choke manifold shall be welded, studded, flanged or Cameron clamp of comparable rating.
- 2. All flanges shall be API 6B or 6BX and ring gaskets shall be API RX or BX. Use only BX for 10 MWP.

2'x5'

4.

- 3. All lines shall be securely anchored.
- 4. Chokes shall be equipped with tungsten carbide seats and needles, and replacements shall be available.
- 5. Choke manifold pressure and standpipe pressure gauges shall be available at the choke manifold to assist in regulating chokes. As an alternate with automatic chokes, a choke manifold pressure gauge shall be located on the rig floor in conjunction with the standpipe pressure gauge.
- 6. Line from drilling spool to choke manifold should be as straight as possible. Lines downstream from chokes shall make turns by large bends or 90° bends using bull plugged tees.
- 7. Discharge lines from chokes, choke bypass and from top of gas separator should vent as far as practical from the well.