

8. Testing Logging and Coring Programs:

- DST's: DST any mudlog shows.
- Logging: 2-man Mudlogging unit from 3200' to T.D.
- Electric Logs: Platform Express with CNL-LDT, DLL-MSFL, GR and Caliper.
- Coring: None anticipated

9. Abnormal Pressure, Temperatures or Other Hazards: Lost circulation is anticipated in the surface and intermediate holes. Maximum bottomhole pressure is estimated to be 4200 psig.

10. Anticipated Starting Date: September 1, 1999.