

6. Source of Construction Materials:

All caliche required for construction of the drill pad and the proposed new access road will be obtained from a BLM approved caliche pit. All roads and pads will be constructed of 6" rolled and compacted caliche.

7. Methods of Handling Water Disposal:

- A. Drill cuttings not retained for evaluation purposes will be disposed into the reserve pit.
- B. Drilling fluids will be contained in steel mud tanks. The reserve pit will contain any excess drilling fluid or flow from the well during drilling, cementing and completion operations. The reserve pit will be an earthen pit approximately 150' x 150' x 6' deep and fenced on three sides prior to drilling. The fourth side will be fenced immediately following rig removal. The reserve pit will be plastic lined (5-7 mil thickness) to minimize loss of drilling fluids and saturation of the ground with brine water. Drilling fluids will be allowed to evaporate in the reserve pits until dry.
- C. Water produced from the proposed well during completion may be disposed into the reserve pit or a steel tank (depending upon rates). After the proposed well is permanently placed on production, produced water will be collected in tanks (fiberglass or steel) until hauled to an approved disposal system or a separate disposal application will be submitted to BLM for approval. Produced oil will be collected in steel tanks until sold.
- D. A portable chemical toilet will be provided on the location for human waste during the drilling and completion operations. Compliance with current laws and regulations pertaining to the disposal of human waste will be followed.