

YATES PETROLEUM CORPORATION
Louise "AYT" #1
Drilling Prognosis
Page 2

MUD PROGRAM: 0-600'; Freshwater, WT 8.6-8.9, VIS 30-36, WL N/C.
600'-2700'; Freshwater/LCM Sweeps, WT 8.4-8.9,
VIS 28, WL N/C.
2700'-8900'; Cut Brine, WT 8.6-8.9, VIS 28; WL N/C.
8900'-10100'; Cut Brine/Starch, WT 9.0-9.8, VIS 28, WL N/C.
10100'-12000'; Salt Gel/Starch/Drispac, WT 9.6-10.2, VIS 32-37,
WL <12.

BOPE PROGRAM: 5000 psi BOPE will be installed on the 8 5/8" casing and
tested daily for operational.