

5. Source of Construction Materials:

All caliche required will be obtained from an existing BLM approved pit. All roads and pads will be constructed of 6" rolled and compacted caliche.

6. Methods of Handling Water Disposal:

- A. The drill cuttings, fluids, and completion fluids will be placed in the reserve pit. The reserve pit will be fenced on three sides away from the pad during drilling and the fourth side as soon as the rig moves out. The reserve pit will be allowed to dry. Reserve pit contents will be pushed into adjacent caliche pit and covered with location top soil.
- B. All garbage and trash will be placed in a trash container to be hauled off location.
- C. Chemical toilets will be provided and maintained during drilling operations

7. Ancillary Facilities:

No campsite or other facilities will be constructed as a result of this well.

8. Well Site Layout:

- A. The drill pad is shown on Attachment. Approximate dimensions of the pad, the pits and the general location of the rig equipment are displayed. Top soil will be stored adjacent to the pad until reclamation efforts are undertaken. Only modest cuts will be necessary to build the pad which will be covered with 6" of compacted caliche.
- B. No permanent living facilities are planned, but temporary trailers for the tool pusher, drilling foreman and mud logger may be on location throughout drilling operations.
- C. The reserve pit will be lined using plastic sheeting of 6 mil thickness.

9. Plans for Restoration of Surface:

- A. If well is abandoned, the location and access road will be cleaned and restored to the original topographical contours as much as possible. The area will be reseeded with the appropriate seed mixture.
- B. If the well is productive, areas not used in production will be contoured and seeded with stipulated seed mixture. Production equipment will be painted the color designated by the Bureau of Land Management.