

13 $\frac{3}{8}$ " CASING SET AT 370'
CMTD. W/450 SX. CLASS "H"
W/2% CdCl. CIRC. 30 SX.

13 $\frac{3}{8}$ " CASING CENTRALIZERS
AT 307', 338', 358'

13 $\frac{3}{8}$ "

TOC 2150'

8 $\frac{5}{8}$ "

8 $\frac{5}{8}$ " CASING SET AT 5468'
CMTD. W/1000 SX. TRINITY LW,
250 SX. CLASS H - TOC 2150'

8 $\frac{5}{8}$ " CASING CENTRALIZERS
AT 5219', 5382', 5415', 5445'

8 $\frac{5}{8}$ " SCRATCHERS AT:
5445'-58'

TOC 7950'

5 $\frac{1}{2}$ "

5 $\frac{1}{2}$ " CASING SET AT 11875'
CMTD. W/750 SX. CLASS H W/7 $\frac{1}{2}$ % CFR2
W/5" SALS/CX. - TEMP SURVEY TOC 7950'

5 $\frac{1}{2}$ " CASING CENTRALIZERS
AT:

10,390', 10,640'
10,760', 10,980'
11,500', 11,620'
11,730', 11,850'

5 $\frac{1}{2}$ " SCRATCHERS AT:

10,390'-400', 10,640'-50'
10,760'-70', 10,980'-80'
11,500'-70', 11,620'-80'
11,730'-40', 11,850'-70'

2 $\frac{1}{8}$ " TUBING SET IN MODEL F-1 PACKER
AT 11,470'

ATOKA ZONE - SELECTIVE PERFORATIONS

2 JET SHOTS/FT. 10,685-91', 10,694'-97', 10,744'-50',
10,794'-99'

BFC MODEL "L" SLIDING SLEEVE AT 11,451'

BAKER MODEL "FL" ON-OFF SEALING
CONNECTOR AT 11,455'

BAKER MODEL F-1 PACKER AT 11,470'

MORROW ZONE - SELECTIVE PERFORATIONS

2 JET SHOTS/FT. 11,550'-E4', 11,601'-10', 11,619'-53', 11,669'-73'

PSTD 11,805'

NO.	REVISION	BY	DATE	CHKD	APP'D
FOR BIDS	 PHILLIPS PETROLEUM COMPANY BARTLESVILLE, OKLAHOMA				
FOR APPR					AFE NO. FILE CODE
FOR CONST					SCALE NONE UNLESS OTHERWISE NOTED
DESIGN					DWG NO.
DRAWN	RRB 6/72	UNIT C, SEC 18, T-23-S, R-27-E EDDY COUNTY, NEW MEXICO			
CHECKED	LLF 6/72	SH			