

13 $\frac{3}{8}$ " CASING SET AT 370'
CMTD. W/425 SX. CLASS H W/2% CaCl
1/4" FLOCELE/SX. CIRC. 100 SX.

13 $\frac{3}{8}$ " CASING CENTRALIZERS
AT 291', 330', 360'

8 $\frac{5}{8}$ " CASING SET AT 5450'
CMTD. W/1300 SX. TL.W. W/3#
GILSONITE/SX. AND 250 SX. CLASS H
TEMP. SURVEY - TOC 1900'

8 $\frac{5}{8}$ " CASING CENTRALIZERS AT
5380', 5413', 5445'

8 $\frac{5}{8}$ " SCRATCHERS AT
5430' - 5440'

5 $\frac{1}{2}$ " CASING SET AT 12041'
CMTD. W/550 SX. CLASS H W/34% CFR-2
W/8" CALT/SX. - TEMP. SURVEY TOC 7800'

5 $\frac{1}{2}$ " CASING CENTRALIZERS AT
10,760', 10,820', 10,720'
10,670', 11,740', 11,490'
11,892', 11,952', 12,025'

5 $\frac{1}{2}$ " SCRATCHERS AT
10,200'-70', 10,310'-20', 10,720'-30',
10,800'-70', 11,450'-60', 11,675'-65',
11,730'-40', 11,800'-10', 11,955'-65'

13 $\frac{3}{8}$ "

TOC 1900'

8 $\frac{5}{8}$ "

TOC 7800'

5 $\frac{1}{2}$ "

2 $\frac{7}{8}$ " TUBING SET IN MODEL F-1
PACKER AT 11,380'

CANYON ZONE - SELECTIVE PERFORATIONS
2 JET SHOTS/FT. 10,280' - 10,300'

BAKER MODEL "L" SLIDING SLEEVE AT 11,300'

BAKER MODEL "FL" ON-OFF SEALING
CONNECTOR AT 11,375'

BAKER MODEL F-1 PACKER AT 11,380'

MORROW ZONE - SELECTIVE PERFORATIONS
2 JET SHOTS/FT. 11,468' - 78', 11,668' - 74',
11,685' - 90', 11,702' - 69', 11,718' - 21'

PBTD 11,970'

NO.	REVISION	BY	DATE	CHKD	APP'D
FOR BIDS	PHILLIPS PETROLEUM COMPANY				AFE NO.
FOR APPR	BARTLESVILLE, OKLAHOMA				FILE CODE
FOR CONST	DRAG "B" #1				SCALE NONE UNLESS OTHERWISE NOTED
DESIGN	UNIT K, SEC 18, T-23-S, R-27-E				DWG NO.
DRAWN RFE 8/72	EDDY COUNTY, NEW MEXICO				SH NO.
CHECKED LLF 8/72					
APP'D					