

13 $\frac{3}{8}$ " CASING SET AT 397'

CMTD. W/450 SX. CLASS H W/2% CaCl
1/4" FLOCELE/SX. CIRC. 50 SX.

13 $\frac{3}{8}$ " CASING CENTRALIZERS
AT 333', 392'

8 $\frac{5}{8}$ " CASING SET AT 5511'

CMTD. W/1200 SX. T.L.W. W/3#
GILSONITE/SX. AND 250 SX. CLASS H
TEMP. SURVEY - TOC 1630

8 $\frac{5}{8}$ " CASING CENTRALIZERS AT
5372', 5423', 5505'

8 $\frac{5}{8}$ " SCRATCHERS AT
5495-5505'

5 $\frac{1}{2}$ " CASING SET AT 11,984'

CMTD. W/550 SX. CLASS H W/3/4% CFR-2
W/8" SALT/SX. - TEMP. SURVEY TOC 9250'

5 $\frac{1}{2}$ " CASING CENTRALIZERS AT

11965', 11830', 11810', 11660', 11575', 11495', 11470', 11410'
11080', 11020', 10950', 10770', 10750', 10270', 9660',
9640', 9400'

5 $\frac{1}{2}$ " SCRATCHERS AT

11965-75', 11830-40', 11800-10', 11660-70',
11565-75', 11495-505', 11460-70', 11400-410',
11080-90', 11010-20', 10940-50', 10770-80',
10740-50', 9660-70', 9630-40'

3 $\frac{3}{8}$ "

TOC 1630'

8 $\frac{5}{8}$ "

TOC 9250'

5 $\frac{1}{2}$ "

2 $\frac{7}{8}$ " TUBING SET IN MODEL F-1
PACKER AT 11,300'

ATOKA ZONE - SELECTIVE PERFORATIONS
4 JET SHOTS/FT. 10748-54'

BAKER MODEL "L" SLIDING SLEEVE AT 11,28'

BAKER MODEL "FL" ON-OFF SEALING
CONNECTOR AT 11,296'

BAKER MODEL F-1 PACKER AT 11,300'

MORROW ZONE - SELECTIVE PERFORATIONS
2 JET SHOTS/FT. 11412-23', 11426-36', 11480-88',
11546-50', 11611-21', 11632-42', 11652-58',
11814-84'

PBTD 11,902'

NO.	REVISION	BY	DATE	CHKD	APP'D
FOR BIDS		TEXAS INTERNATIONAL PETROLEUM CORPORATION			AFE NO.
FOR APPR					FILE CODE
FOR CONST		TIDWELL - A "COM"			SCALE NONE UNLESS OTHERWISE NOTED
DESIGN					DWG NO.
DRAWN	RFH 8/72	UNIT E, SEC. 8, T-23-S, R-27-E			SH NO.
CHECKED	LLF 8/72	EDDY COUNTY, NEW MEXICO			
APP'D					