

TEXACO INC.  
WHITE CITY (COM) NO. 1  
REVISED CASING AND CEMENTING PROGRAM

HOLE SIZE	CASING SIZE	WEIGHT	DEPTH	CEMENT
20"	16"	55#	40'	Ready Mix
15"	10 3/4"	32.75#	1650'**	1500 sx
8 1/2"	7 5/8"	26.4#	8000'***	1400 sx
6 1/2"	4 1/2"	11.6,13.5#	11,550'****	550 sx

\*Conductor Pipe - Reddy Mix Cement

\*\*Surface Casing - Set "DV" tool at 750', 1st. Stage: 400 sx TLW 12 ppg followed by 300 sx class "C" neat 14.8 ppg. 2nd Stage: 700 sx TLW 12ppg followed by 100 sx Class "C" neat 14.8 ppg (300% to circulate - Must circulate)

\*\*\*Intermediate Casing - Set "DV" tool at 5000'. 1st Stage: 500 sx TLW 12 ppg followed by 200 sx Class "C" neat 14.8 ppg. 2nd Stage: 600 sx TLW 12 ppg followed by 100 sx Class "C" neat 14.8 ppg. (Run baskets below "DV" tool.) 150% to tie back - not required.

\*\*\*\*Production Liner - 550 sx Class "H" w/.5% Halad 9 15.6 ppg. Squeeze top if necessary. Run thickening test with rig water prior to cementing.

**RECEIVED**  
SEP 26 1973  
U. S. GEOLOGICAL SURVEY  
ARTESIA, NEW MEXICO

AMENDMENT TO  
EXHIBIT "F"