

2ND TESTHO-1257R (4)
PAGE 3

RECOMMENDED WORK PROCEDURE

PAGE 2 OF 2

EASE MAUDE RICKMAN COM WELL NO. 1

ANNULAR FLUID PRIOR TO WORKOVER 4% KCL TRTD W/ APP. PKR FLUID W/O FLUID TO BE USED 9.5#/GAL MLF

WT. (LBS/GAL.) 9.5 ZONE WOLF CAMP HYD. PRESS 5037 RES. PRESS N/A

ZONE HYD. PRESS RES. PRESS

ZONE HYD. PRESS RES. PRESS

ALTERNATE WOLF CAMP TEST IF PRIMARY TEST IS UNPRODUCTIVE

NOTIFY L.A. CLEMENTS 24 HRS PRIOR TO BEGINNING WORK (505-748-1283).

- 1 KILL WELL W/ 9.5#/GAL MLF. N/D WELLHEAD NUBOP
- 2 RELEASE BAKER LOK-SET PKR @ $\pm 10,120'$ $\pm$ POH
- 3 GIH W/ 7"-26#/FT GR & JB TO 10,120' POH
- 4 GIH W/ 7"-26# CIBP ON WIRELINE & SET @ 10,110 (COLLARS 10,100', 10,143'*) POH
- 5 GIH W/ DUMP BAILER & DUMP 85X(50') CL.C CMT W/ DUMP BAILER. POH TOC = 10,060
- 6 PRESSURE TEST CASING & PLUG TO 1000 PSI FOR 15 MIN. REQ. BY NMCC.
- 7 GIH W/ BAKER 7"-26# LOK-SET PKR + "EL" TBG. SEAL RECPT. + 2 3/8" EVE BRO N-80 TBG TO $\pm 10,000'$. TEST TBG TO 2000 PSI GIH.
- 8 REVERSE CIRCULATE HOLE CLEAN W/ 4% KCL WATER TREATED W/ APP. PKR. FLUID (LISTED BELOW).
- 9 PULL UP & SET PKR @ ± 9740 (COLLARS 9719', 9761'*) TEST ANNULUS TO 1000 PSI
- 10 N/D BOP, N/D WELLHEAD
- 11 GIH W/ THRU TBG PERF GUN (TOP & BOTTOM DECENTRALIZED) & PERFORATE 9712 TO 9810 & 9838 TO 9846 & 9874 TO 9878 W/ 1-JSPF (PREMIUM CHARGES). 33 HOLES *
- 12 SWAB/FLOW WELL FOR EVALUATION. CATCH FLUID SAMPLES FOR COMPATIBILITY TESTS.
- 13 IF NECESSARY, STIMULATE W/ 6600 GAL. DINE FE 15% HCL W/ FRICTION REDUCERS, FOAMERS, & CLAY STABILIZERS, FOAMED TO 70 QUALITY FOAM W/ N₂. DROP 50 BALLS 1.1 SG
- 14 SWAB/FLOW WELL BACK IMMEDIATELY UNTIL ALL LOAD IS RECOVERED.
- 15 PUT ON TEST & EVALUATE FOR PRODUCTION.
- 16 RD & REL DU

* WESTERN Co GR-CCL 4-15-74

PROCEDURE GIVEN BY L.A. CLEMENTS NMCC ARTESIA

W/ L REEVES

PK FLUID: NL COAT B-1400, TRET. KW-32, CHAMP. CORTRON 2207, UNICHEM TECHNI-HIB 370