

AVALON HILLS NO. 1

MUD PROGRAM

Surface: 0 - 600'
Fresh water gel/lime slurry

Intermediate: 600 - 3000'
Fresh water with L.C.M. for seepage

Production: 3000' - T.D.
Fresh water and lime to 8500'.
At 8500' mud up with a fresh water low solids
Benex system (Wt. 8.9 to 9.2#/Gal.)
At 10,000' increase weight to 9.7#/Gal.
Adjust weight and viscosity as required to T.D.
Reduce water loss to 5 cc before drilling Morrow.